

Hanwha Solutions

To complete the system commissioning successfully, you **must** complete the following **three steps** with the **Hanwha** monitoring platform **Q.ommand Pro App** or **Q.OMMAND** (qcells.com).

Step 1

Enter the inverter serial number, NMI and select 'Synergy' as the 'Retailer' field.

Enter required information

Install Type: Hybrid

Device Type: PV Module

Serial No.: Enter an available serial No.

Model Name:

NMI No.:

Retailer: None

NEXT

Step 2

Complete the customer registration in **Q.ommand** and ensure the inverter is connected to the customer's local network.

Top Tips

- Ensure you have selected the correct grid code for Australia Region B (AS/NZS 4777.2:2020) during the commissioning process.
- Need further assistance contact **support@qhome.email**